

NOTICE INVITING QUOTATIONS

NIQ.No.02/TGSTP/EW/2025-26, Dt. 20.01.2026

Sealed quotations are invited on behalf of The Chairman, TGSTEP, Hyderabad from approved and eligible contractors for the following works:

| Sl. No. | Name of work | Start date & time for sale of Quotation Document | Last date & time for bidding |
|----------------|---|---|---|
| 1. | Waterproofing of terrace slab of TGSTEP & DYS office complex (AP wing) at Boats club , Secunderabad | 20.01.2026 From 10.30 AM | 28.01.2026 Up to 3:00 PM. |

1. Schedule of quantities with terms & conditions may be downloaded from TGSTEP Website www.tsstep.in
2. Quotations (price bid) along with the following documents have to be submitted in TGSTEP office by the above due date.
 - a) Civil Engineering Contractors registration Class-V and above.
 - b) GST Registration copy.
 - c) PAN Card copy.

Terms & conditions

1. Payment will be made as per actual quantities executed after completion of work.
2. GST TDS & IT TDS will be deducted as per norms.
3. Defect Liability period will be One(1) Year from the date of completion.
4. Future Security Deposit (FSD) @ 5% of value of work will be deducted from payment (or) The bidder may furnish Bank Guarantee towards FSD for releasing full amount.
5. Any additional item carried out as per site requirement will be paid as per Standard Schedule of Rates, Government of Telangana or lowest market rates.

QUOTATION**Name of Work: Waterproofing of terrace slab of TGSTEP & DYS Office complex (AP wing) at Boats Club , Secunderabad**

| Sl. No. | Item | Qty | Unit | Rate | Amount |
|----------------|--|------------|-------------|------------------|---------------|
| 1 | Dismantling and conveyance of damaged waterproofing surface over the existing slab with CC breaker on terrace and disposing the debris material with a lead of 20KM including all charges for machinery and labour etc complete. | 520 | Sqm | | |
| 2 | Expansion joint treatment to existing slab surface: Removing dead mortar on both sides up to 300 mm, application of two component epoxy adhesive covered with flexible thermo plastic elastomeric expansion joint tape with fiber mesh reinforcement using flexi tape and construction of brick walls on both sides of expansion joint plastering and covering with shabad slabs complete for item of work. | 18 | Rmt | | |
| 3 | Terrace Water Proofing - Surface area chipping with hammers and chipping machine, cleaning with wire brush and removing dust particles with electric blower. Finding the cracks and cutting with electric machine 1.25 mm V groove, removing dust particles and filling with "FOSROC EP 10" compound and pressure grouting the old slab with cement and chemical mix by fixing nozzles wherever necessary, top slab surface area coated with "SBR LATEX" with 2 coats, flooring with sand, cement mortar (1:3) mixed with the "FOSROC WL" maintaining proper slope, finishing top surface area with neat cement slurry and providing grid lines with 10mm thread maintaining with 2'X2" gap complete for finished item of work. | 520 | Sqm | | |
| | | | | Sub total | |
| | | | | GST@18% | |
| | | | | Total | |

Signature of the Bidder