

NOTICE INVITING QUOTATION

NIQ.No.06/TSSTEP/EW/2022-23, Dt. 07 .12.2022

Sealed quotations are invited by the Chairman, TSSTEP from approved and eligible contractors for the following works.

Sl. No.	Name of Work	Time Allotted	Start date & time for sale of quotation document	Last date & time for sale of quotation document	Last date & time for bidding.
1	Painting and Water proofing works for TSSTEP Skill Development Training Centre, Hanamkonda	15 days	07.12.2022	14.12.2022 upto 2:00 PM	14.12.2022 upto 3:00 PM

Quotation documents shall be considered valid of only those contractors who will submit the **attested copies** of the following documents within the period of bid submission:

- (i) Civil Engineering Contractors registration with Govt of Telangana
- (ii) Registration of GST.
- (iii) PAN Card

The quotation for the work/supply shall remain open for a period of 7 days from the date of opening of quotations.

Encl: Schedule of Quantities with terms & conditions.

Sd/-
Chairman

SCHEDULE OF QUANTITIES

Name of work: Painting and Water proofing works for TSSTEP Skill Development Training Centre, Hanamkonda

Sl No	Description of Items	Qty	Unit	To be Quoted by Agency	
				Rate	Amount
	Civil Items				
1	Internal painting-Painting to internal walls/Ceiling with 2 coats of Acrylic based Oil bound Washable Distemper having VOC content less than 50 grams/litre over primer coat using water based cement primer of interior grade-1 making 3 coats in all to give an even shade after thoroughly brushing the surface to remove all dirt and remains of loose powdered materials, including cost and conveyance of all materials to work site and all operational, incidental, labour charges etc., and overheads & contractors profit complete for finished item of work as per APSS 911 for internal walls/ceiling in all floors.	1051.41	Sqm		
2	External painting-Supply & application of one coat water based cement primer of exterior grade II and two coats of acrylic emulsion paint exterior grade with silicon additives having VOC (Volatile Organic Compound) content less than 50 grams/ litre for exterior walls including cost and conveyance of all materials to site, sales & other taxes, incidental, operational and all labour charges etc., and overheads & contractors profit complete for finished item of work in all floors.	390.17	Sqm		
3	Water proofing over terrace with roof guard	536.00	Sqm		
4	Water proofing treatment to outside walls	623.72	Sqm		
5	Flooring with soluble salt porcelain vitrified tiles screen printed and polished of size 600 x 600 mm and thickness between 8 to 10mm 1st quality conforming to IS: 13711, IS: 13712, IS: 13630(Parts 1 to 15) of any colour and finish in all shades and designs with borders and design as per the approved flooring pattern as directed by the Engineer-In -Charge, laying tiles using spacers of 2mm thick, set over a base coat of CM (1:8) prop. 12mm thick using screened sand over CC bed already laid or RCC roof slab, including neat cement slurry of honey like consistency spread @ 3.3 kgs per Sqm. and jointed neatly with white cement paste to full depth mixed with pigment of matching shade including cost and conveyance of all materials like cement, sand, water, tiles, white cement etc., to site (excluding cost of C.C. bed) including cost of base coat and all labour charges for mixing of cement mortar, laying tiles to required slope as directed by the Engineer- in-charge etc., and overheads & contractors profit complete for finished item of work. (APSS No.701 & 707)	392.94	Sqm		

6	Plain Cement Concrete (1:4:8) (cement: fine aggregate: Coarse aggregate) for foundations and under flooring bed using coarse aggregate 40mm size hard , machine crushed granite from approved quarry including cost and conveyance of all materials like cement, sand, coarse aggregate, water etc. to site, including sales & other taxes on all materials and including all charges for machine mixing, laying concrete in foundations and under flooring bed, ramming in 15 cm layers finishing top surface to the required level curing etc., and overheads & contractors profit complete for finished item of work. (APSS No. 402)	1.86	Cum		
7	Brick work-Brick masonry for panel walls in superstructure with CM (1:6) prop: (Cement : Screened sand) using common burnt clay bricks of class as per Table- I of IS:1077-1992, Non- Modular or traditional size 23 x 11 x 7 cms from approved source having minimum crushing strength of 40 Kg/Sqcm. including cost and conveyance of all materials like cement, screened sand, bricks, water etc., to site, including sales & other taxes on all materials and such as labour charges, like mixing cement mortar, scaffolding charges, constructing masonry, lift charges, curing, etc., and overheads & contractors profit complete for finished item of work. (APSS No. 501 & 504).	8.26	Cum		
8	Plastering -Plastering 12mm thick in two coats using screened sand with base coat of 8mm thick in CM (1:6) and top coat of 4mm thick in CM (1:4) with dubara sponge finishing including cost and conveyance of all materials like cement, sand, water etc., to site, including sales & other taxes on all materials, and all operational, incidental charges on materials and including cost of all labour charges for mixing mortar, finishing, scaffolding, lift charges, curing, including cutting grooves as directed by Engineer - in - charge etc., and overheads & contractors profit complete for finished item of work. (SS 901,903 & 904)	242.78	Sqm		
9	Supply and laying of Gravel-Filling with carted gravel all-round the building with initial lead in layers not exceeding 15cm thick, watering and ramming including cost and conveyance of water to work site and all operational, incidental, labour charges, hire charges of T&P etc., and overheads & contractors profit complete for finished item of work(APSS NO.309&310)	228.54	Cum		
10	M20-Plain Cement Concrete M 20 design mix using WEIGH BATCHER / MIXER, 20mm size hard granite machine crushed graded metal (coarse aggregate - as per IS 383 - 1970 and IS 2386 Part 1 to Part 8) from approved quarry, using a minimum quantity of 350 kgs. of cement per 1 cum of concrete including cost and conveyance of all materials like cement, fine aggregate (Sand), coarse aggregate, water etc., to site including steel centring, shuttering, machine mixing, lift charges, laying concrete, vibrating, curing, overheads & contractors profit etc., complete for finished item of work (APSS No. 402 & 403)	16.81	Cum		

Contd..3..

11	Parking Tiles-Flooring with chequered cement concrete heavy duty tiles confirming to IS:13801 using aggregates, cement, pigments of size 300mm x 300mm and thickness 25mm of any shade as approved by Engineer - In - Charge set over base coat of cement mortar (1:6), 12 mm thick using screened sand over CC bed already laid or RCC roof slab including neat cement slurry of honey like consistency spread @ 3.3 kgs per sqm and jointed with neat white cement to full depth mixed with pigment of matching shade including cost and conveyance of all materials like cement, sand, water and tiles etc., and overheads & contractors profit complete for finished item of work.	27.66	Sqm		
12	RR Masonry-Random Rubble stone masonry in CM (1:8) prop: (Cement: Screened sand) using hard granite stones carted from approved quarry including cost and conveyance of all materials like cement, screened sand, water, stones etc., from approved quarry, to site, sales & other taxes on all materials including labour for cutting stones to required size and shape, mixing, of cement, mortar, construction, curing etc., and overheads & contractors profit complete for finished item of work	5.96	Cum		
13	New chajjas -RCM facia 50mm thick using screened sand for drop walls, fins with rabbit wire mesh & nominal reinforcement as directed by Engineer - In - Charge with dubara sponge finishing, including cost and conveyance of all materials to site, sales & other taxes on all materials, operational & incidental, cost and conveyance of cement, wire mesh, water to work site, centring, scaffolding and form work, lift charges etc., and overheads & contractors profit complete for finished item of work but excluding cost of steel and its fabrication charges for finished item of work (APSS NO.403&903)	6.59	Sqm		
14	Steel-TMT-8mm-Providing Thermo Mechanically Treated (TMT) (Fe 500 grade as per IS 1786-1979) (Tata, SAIL, VSP, JSW & Shyam Steel) of different diameters for RCC works , including labour charges for straightening, cutting, bending to required sizes and shapes, placing in position with cover blocks of approved materials and size and tying and lap-splicing with binding wire of 18 SWG, forming grills for reinforcement work as per approved designs and drawings, including cost and conveyance of steel bars, including all wastages such as overlaps, couplings, chairs, spacer bars including cost and conveyance of binding wire, cover blocks and all incidental, operational, labour charges such as cutting, bending, placing in position, tying including sales and other taxes on all materials etc. ,and overheads & contractors profit complete for finished item of work.(APSS No.126)	0.25	MT		
	Sub Total				
	GST @12%				
	Total				

Contd..4..

Terms & Conditions:

1. The work shall be carried out as per APSS specification and as direction of Engineer-in-charge.
2. Time allowed for executing the work is **15 days**.
3. No T & P shall be provided by the department.
4. Payment will be released after satisfactory completion of the work. FSD at 2.50% and IT as applicable will be recovered from the bill
5. TDS on GST at 2% will be deducted and paid in to the GST account of the agency

(To be filled by the Agency)

Total amount quoted by the agency

(Including GST at 12%): _____

Signature of the bidder: _____

Name of the Agency: _____

Mobile No: _____

Correspondence Address: _____
